

**Project Factsheet** March 27, 2020



#### Project Milestones

##### Contract Award

December 23, 2019

##### Target Construction Schedule

Spring 2020 - Fall 2020

##### Contractor

J. HUTCHINS, INC.

##### Estimated Cost

\$1,930,699.27



Northbound Begin Project MM 6.006



Southbound End Project MM 7.263



Lord's Prayer Rock

## BRISTOL

### STP PC20(2)

**Class 1 paving in the town of Bristol on VT 116.**

#### Project Location:

0

Beginning on VT Route 116 in Bristol near the intersection of Airport Road at mile marker 6.006 then running north for 1.230 miles and ending at Class I/State Highway limit at mile marker 7.263 in Bristol.

#### Project Description:

0

Work will consist of coarse milling the existing pavement to a 2" depth, then placing a 1/2" lift of Type IVS pavement to level the road surface, followed by a 1-1/2" lift of Type IVS pavement as the final wearing surface. Prior to the placement of the final wearing surface utility valves and drainage structures within the roadway will be adjusted as necessary. Sidewalk ramps and pedestrian crossing infrastructure will be replaced and upgraded to meet current ADA standards. Some minor drainage work will occur near and along the edge of pavement. Signs will also be replaced and upgraded as necessary to meet current specifications in the Manual on Uniform Traffic Control Devices (MUTCD). This project is incorporated under a larger composite contract with the Vergennes STP PC20(1) Class I paving project.

This project is also administering a local project known as the *Bristol Main Street Lighting & Sidewalk Project*. This work begins near the intersection of North Street/South Street/Main Street and extends northerly to a point near the National Bank of Middlbury. This work entails new sidewalk, imprinted concrete and curbing on the east portion of Main Street. The west side of Main Street will receive new curbing and imprinted concrete. The existing street lighting system will be replaced in-kind with new electrical conduit, foundations/concrete pedestals and light fixtures.

#### Project Timeline:

0

Construction will begin in the spring months of 2020 and will end in the fall of 2020. Work between the intersection of North Street/South Street/Main Street to a point near the National Bank of Middlbury at mile marker 6.719 will be done between the hours of 7:00 pm and 6:00 am the next calendar day.

## Contact Information

#### Public Information Consultant

Natalie Boyle

(802) 855-3893

nboyle@eivtech.com

[Contact VTrans \(https://vtrans.vermont.gov/contact-us\)](https://vtrans.vermont.gov/contact-us)



Main Street and Town Green



Main Street