

BRISTOL, VERMONT ANNUAL WASTEWATER SYSTEM EVALUATION 2022-2023

INDIRECT DISCHARGE PERMIT ID 9-0208-1

Prepared By: VTM Engineering, PLC

Date: May 31, 2023

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

**BRISTOL, VERMONT
ANNUAL WASTEWATER SYSTEM EVALUATION
2022-2023**

TABLE OF CONTENTS

1.0	INTRODUCTION
2.0	WASTEWATER SYSTEM INSPECTION
2.1	Wastewater Collection System Inspection
2.2	Wastewater Treatment System Inspection
2.2.1	Septic Tank Inspection
2.2.2	Splitter Box Inspection and Disposal Field Rotation
2.2.3	Dosing Siphon Inspection
2.3	Wastewater Disposal Field Inspection
3.0	WASTEWATER SAMPLING AND EFFLUENT TESTING
4.0	GROUNDWATER SAMPLING AND TESTING
5.0	WASTEWATER FLOW
6.0	UNCOMMITTED RESERVE CAPACITY
7.0	SUMMARY AND CONCLUSIONS

APPENDICES

APPENDIX A - Figures

Figures 1 & 2 - Collection System Component Locations
Figure 3 - Disposal Area Components
Figure 4 - Septic Tank Detail

APPENDIX B - 2021 Wastewater Discharge and Monitoring Well Sampling Results

APPENDIX C – 2021/2022 Wastewater Treatment System Flow Data

APPENDIX D – Uncommitted Reserve Capacity Calculations

APPENDIX E - Photographs

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

1.0 BACKGROUND

The Town of Bristol, Vermont owns and operates a sewage collection, treatment and disposal system located in the downtown core of Bristol village. The system collects and treats wastewater from approximately thirty-four (34) individual commercial and residential properties within the “core” business district. The wastewater collection and disposal system are governed by Indirect Discharge Permit number 9-0208-1 issued by the State of Vermont. The Permit was re-issued in November 2022.

The system has been operating since September 1, 1993. The system consists of a wastewater collection system, a septic tank, disposal fields and associated appurtenances. An annual inspection of the collection and disposal system by a registered professional engineer is required to be conducted during the month of April as a condition of the Indirect Discharge Permit. The Town of Bristol contracted with VTM Engineering, PLC (VTM) of Hinesburg, Vermont to conduct the annual wastewater inspection and evaluation.

The annual inspection of the Bristol wastewater collection, treatment and disposal system was performed on April 15, 2023 by Steven Palmer, P.E. of VTM. Mr. Palmer performed the inspection in conjunction with Mr. Cyrus Marsano of Vermont Utility Management Services (VTUMS). VTUMS is the licensed wastewater operator for the Bristol Wastewater System.

This Report outlines the items inspected, the observations made, analysis of annual sampling and testing data as well as recommendations for repairs and/or operations.

2.0 WASTEWATER SYSTEM INSPECTION

The Bristol Wastewater system is comprised of three major components:

- 1) a wastewater collection system comprised of collection manholes, grease traps and piping;
- 2) a septic tank, splitter box and dosing siphons;
- 3) eight separate wastewater disposal fields.

The original wastewater system design envisioned four of the eight disposal fields being in operation at any given time. The original design envisioned a flow of 5,000 gpd maximum capacity to each of four operating fields (20,000-gallon total hydraulic capacity). Later permit amendments also applied biological loading criteria limitations including TSS and BOD⁵.

Figures 1, 2 and 3 Appendix A show the general location of the major system components.

2.1 Wastewater Collection System Inspection

The Discharge Permit requires inspecting the collection system including removing manhole covers to observe the condition of sewers and manholes, and noting any signs of inflow or excess infiltration.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

A summary of the individual wastewater collection system observations by component are presented in Table 1.

The municipal wastewater collection system consists of twelve concrete collection manholes and approximately 1,500-feet of wastewater collection piping. It should be noted that a number of the restaurants connected to this system also have privately owned grease traps inside of each facility which are regulated by the Vermont Health Department and were not a part of this inspection. Six of the restaurants also have separate exterior grease traps as noted in Table 1. It is VTM's understanding that the exterior grease traps are pumped quarterly by Clark Wright Septic Services and that the interior grease traps are maintained independently by each restaurant. VTUMS confirmed that the exterior grease traps are pumped on a quarterly schedule. It is unclear from the information available at the time of the inspection whether or not the interior grease traps are being maintained by the restaurant owners as scheduled.

Sewer manhole covers were removed and each component in the collection system was visually inspected by VTM and VTUMS. A summary of observations made during the wastewater collection system inspection are included in Table 1.

**TABLE 1
BRISTOL WASTEWATER
COLLECTION SYSTEM OBSERVATIONS**

ITEM A	COLLECTION SYSTEM COMPONENT
MH #1	Low flow/good condition/dead end. Shelves should be cleaned.
MH #2	Low flow/good condition.
MH #3	Low flow/good condition. Shelves should be cleaned.
	MH #4 Good condition/low flow. Shelves should be cleaned.
	MH #5 Good condition, low flow/dead end. Shelves should be cleaned.
MH #6	Clean, good condition.
MH #7	Under stone drive. Could not find. Manhole should be found and have a riser added to bring it to surface level.
MH #8	Low flow/gravel on shelves/excellent condition. Drop manhole.
MH #9	Low flow/good condition.
	MH #10 Excellent condition.
	MH #10A Low flow/good condition. Shelves need cleaning.
MH #11	Low flow/good condition.
Mary's Grease Trap - Cannot inspect except during pumping. Quarterly schedule.	
Hendee Grease Trap - Cannot inspect except during pumping. Quarterly schedule.	
Snap's Grease Trap - Cannot inspect except during pumping. Quarterly schedule.	
Bakery Grease Trap - Cannot inspect except during pumping. Quarterly schedule.	
Cubbers Grease Trap- Cannot inspect except during pumping. Quarterly schedule.	

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

Interior Grease Traps (private) - Not Inspected. Operator reports local hauler is cleaning quarterly for the property owners under separate maintenance agreement.
--

Viens Dosing Siphon – Good condition.

2.2 Wastewater Treatment System Inspection

The Bristol wastewater treatment system consists of a septic tank, piping, splitter box, eight dosing siphons as well as eight separate wastewater disposal fields. Four of the eight wastewater disposal fields are in operation at any given time. Bristol's wastewater Discharge Permit requires an annual inspection of each component within the treatment system to ensure proper operation including but not limited to the septic tank including a notation of the accumulation of solids and scum in the septic tank, verification of disposal field rotation, dosing siphon operation, evaluation of the disposal fields including walking the disposal fields and checking for any signs of surfacing effluent or other signs of failure, and finally notation of any repairs or maintenance that needs to be performed including pumping of the structures if necessary.

2.2.1 Septic Tank Inspection

The septic tank cover was removed and the tank was inspected by both VTM and VTUMS personnel. The septic tank is constructed with four separate compartments for sludge accumulation and storage (refer to Figure 4). Sludge and scum measurements for each compartment were conducted by VTUMS personnel during the inspection. Results were as follows:

Sludge Measurements/Observations Cell #1 Sludge Measurements/Observations Cell #2

Compartment #1 – Sludge 30", Scum 18"

Compartment #1 – Sludge 12", Scum 16"

Compartment #2 – Sludge 12", Scum 24"

Compartment #2 – Sludge 12", Scum 0"

A thick crust (approximately 2' thick) was noted on top of Cell #1, compartment #1. This crust appeared to be primarily grease. Several inches of crust was also noted on the top of Cell #1, compartment #2.

Based on VTM's observations, the septic tank slide gates, safety locks and hasps on hatches appear to be in working condition. The hatches are functional but are seeing some wear and may need to be evaluated for replacement in the future. The septic tank outlet trough was noted to be in poor condition and needs re-bricking. Pumping of both compartments in Cell #1 is recommended based on sludge and grease buildup.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

TABLE 2
BRISTOL WASTEWATER SYSTEM
SUMMARY OF TREATMENT SYSTEM OBSERVATIONS

Description	Comments
Septic Tank Inlet	Cell 1 Needs Pumping
Septic Tank Outlet	Eff. Trough Needs Rebuilding
Splitter Box	Good condition
Dosing Siphon #1	VTUMS to Check Operation
Dosing Siphon #2	VTUMS to Check Operation
Dosing Siphon #3	VTUMS to Check Operation
Dosing Siphon #4	VTUMS to Check Operation
Dosing Siphon #5	VTUMS to Check Operation
Dosing Siphon #6	VTUMS to Check Operation
Dosing Siphon #7	VTUMS to Check Operation
Dosing Siphon #8	VTUMS to Check Operation
Disposal Fields #1-8	No issues noted

2.2.2 Splitter Box Inspection and Disposal Field Rotation

The splitter box cover was opened and inspected by VTM and VTUMS personnel.

Observations were as follows:

1. Fields #3, #5, #7 and #8 were observed to be in operation
2. Fields #1, #2, #4 and #6 were observed to be off
3. Appeared to be good even flow between the fields, very little grease observed in splitter box
4. The splitter box and associated piping inside the box appeared to be in good condition.

VTUMS indicated that they conduct regular verification of even flow to the four fields and conduct skimming of grease in the splitter box if needed. VTM observed VTUMS rotating the disposal fields by opening the valves to dormant disposal fields #1, #2, #4 and #6 and closing the valves to operating fields #3, #5, #7 and #8. Fields #1, #2, #4, #6 will be the operating fields for the next 12 months. Once the valves were opened and the previously dormant fields were brought on-line, even flow was observed to each of the four operating fields. No issues of concern were noted within the splitter box.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

2.2.3 Dosing Siphon Inspection

The dosing siphons were visually inspected by VTM and VTUMS personnel. Insufficient flow existed in fields #1, #2, #4 & #6 to determine if the siphons were properly functioning at that time. VTM recommends that VTUMS verify that the siphons are operating properly once they receive sufficient flow.

The siphon counters do not appear to be operational. Green Mountain Engineering (GME) who originally designed the system indicated that the counters have never seemed to function properly. VTM noted that in the 2020/2021 Annual Inspection Report completed by GME, that GME had recommended replacing the existing counters with new mechanical counters when practical. VTM would support this recommendation as it would assist in verifying whether or not each of the siphon's was operating properly.

2.3 Wastewater Disposal Field Inspection

VTM and VTUMS personnel walked each of the eight disposal fields. The disposal field area is neat and clean and appears to be mowed on a regular basis. During last season's inspection, VTM noted that sumac was encroaching on the disposal fields which brings with it the potential for root damage to the disposal fields. In the spring of 2023, VTUMS removed the sumac and graded and re-seeded the impacted areas. The disposal field and surrounding area are now in much better condition and removal of the sumac allows for easier access to the deep monitoring wells. Several box alder trees were noted to be still encroaching on the disposal fields. These trees should be removed as time allows. Regular mowing of the disposal fields and surrounding areas should be continued.

A discharge pipe for a private stormwater or groundwater drain line was noted which daylights along the bottom of the bank adjacent to the northwest side of disposal Field #1. This line was observed to have a steady flow of water that was discharging on the ground adjacent to the northwest corner of Disposal Field #1. A small diversion ditch should be installed west of disposal field #1 to encourage the water to flow in a northwesterly direction away from the disposal fields.

Locks were noted to be absent from each of the four deep monitoring well enclosures. Locks should be added to these wells.

Each disposal field contains 3-4 shallow observation wells to assist in monitoring potential standing water within the disposal fields. Each of the shallow monitoring wells is approximately 1.5 – 2.0 deep. Each shallow monitoring well contained a cover which was removed during the inspection. A flashlight was utilized to visually identify whether each well was dry or if wastewater was visible. No standing water was noted in any of the shallow monitoring wells in all eight disposal fields. VTM's observations are further summarized in Table 3.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

TABLE 3
BRISTOL WASTEWATER SYSTEM
SHALLOW OBSERVATION WELL MONITORING

<u>Disposal Field</u>	<u>Observation</u>
#1	Dry
#2	Dry
#3	Dry
#4	Dry
#5	Dry
#6	Dry
#7	Dry
#8	Dry

Three deep monitoring wells also surround the eight wastewater disposal fields (wells #2, #3 and #4). These wells are used to monitor existing groundwater levels within the vicinity of the eight disposal fields. Groundwater elevations can be utilized to verify vertical separation between the bottom of the disposal fields and the existing groundwater table. Groundwater levels in the three wells were obtained and reported by VTUMS personnel during June and September 2022. Table 4 summarizes this information. Based on the information provided, there appears to be adequate separation between the bottom of the disposal fields and the existing water table. It is advised for future reporting that the top of monitoring well elevations as well as bottom of shallow well elevations (bottom of the disposal fields) be established and the information be reported based upon a USGS datum.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

TABLE 4
BRISTOL WASTEWATER SYSTEM
DEEP MONITORING WELL MEASUREMENTS¹

Date	Well #	Depth to Groundwater (ft)
6/3/22	2	18.2
	3	33.1
	4	38.8
6/10/22	2	17.1
	3	32.5
	4	39.7
6/17/22	2	18.1
	3	33.3
	4	40.1
6/24/22	2	18.1
	3	33.2
	4	39.9
9/2/22	2	19.0
	3	34.1
	4	40.5
9/9/22	2	18.7
	3	34
	4	40.5
9/16/22	2	18.8
	3	34.1
	4	40.6
9/23/22	2	18.9
	3	33.1
	4	39.9
9/30/22	2	18.5
	3	33.6
	4	40.3

1. Groundwater level measurements provided by VTUMS.

3.0 WASTEWATER SAMPLING & EFFLUENT TESTING

Effluent sampling was performed by VTUMS during June and September 2022. As outlined in the Discharge Permit, VTUMS obtained representative wastewater samples from the Splitter Box. Wastewater samples were subsequently submitted to Endyne Environmental Laboratories for analysis. A summary of the most recent 2022 data as well historic laboratory data since 2020 is provided in Table 5 for reference.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

TABLE 5
BRISTOL WASTEWATER SYSTEM
EFFLUENT TESTING SUMMARY
(Sampling Conducted in Splitter Box)

Sampling Date	June 18, 2020	Sept. 15, 2020	June 21, 2021	Sept. 9, 2021	June 7, 2022	Sept 13, 2022
pH	6.2	6.9	6.28	6.48	6.32	6.6
Chloride	69	74	82	64	60	67
Nitrogen, Ammonia	NR	NR	NR	NR	NR	NR
Nitrogen, Nitrite	0.22	<0.20	<0.20	<0.20	<0.20	<0.20
Nitrogen, Nitrate	<0.20	<0.20	<0.20	<0.20	<0.20	<0.20
TKN	63	61	74	<0.64	50	69
Tot. Dissolved Phosphorous	8.6	8.7	9.7	7.0	4.8	7.2
Biochemical Oxygen Demand (5-day)	560	490	640	420	670	430
Total Suspended Solids	70	86	90	66	86	124
Oil and Grease	32.3	37.1	37.1	37.1	31.3	32.2

Notes:

1. Wastewater quality results are reported in milligrams per liter (ppm) unless otherwise specified.
2. Wastewater quality results are for samples from the splitter box (after septic tank).
3. NR = Not reported
4. laboratory information from 2020 as reported by Green Mountain Engineering.
5. Laboratory sampling conducted by Vermont Utility Management Services (VTUMS)
6. Copies of the laboratory testing data sheets are contained in Appendix B.

Historic laboratory testing data shows that all parameters are well within the anticipated normal ranges for commercial/residential wastewater. No significant variations in parameters were noted from year to year which would indicate a substantive change in the wastewater makeup or strength over this time period.

Nitrite levels in the groundwater samples have significant variability. No clear trend appears to be visible. It is advised to continue to monitor these levels for substantive changes or trend lines.

4.0 GROUNDWATER SAMPLING & TESTING

The Discharge Permit requires that groundwater sampling and testing be performed on deep monitoring wells #3 and #4 during June and September of each year. Groundwater sampling was performed by VTUMS during June and September 2022. Representative water samples

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

from Monitoring Wells #3 and #4 were submitted to Endyne Environmental Laboratories for analysis. A summary of the laboratory data from 2020 - 2022 is provided in Table 6. Copies of the individual laboratory testing data sheets for 2022 are contained in Appendix B.

TABLE 6
BRISTOL WASTEWATER SYSTEM
GROUNDWATER WELL TESTING SUMMARY
(Sampling Conducted in Monitoring Wells #3 & #4)

Monitoring Well # & Date Sampled	pH	E. Coli (MPN/100ml)	Chloride	Nitrate as N	Tot. Dissolved Phosphorous
MW – 3 (June 18, 2020)	6.75	<1.0	7.4	1.3	0.008
MW – 3 (Sept. 15, 2020)	6.86	<1.0	8.8	0.16	0.006
MW-3 (June 21, 2021)	6.93	<1.0	11	1.4	0.007
MW-3 (Sept. 9, 2021)	6.68	<1.0	9.0	<0.20	0.008
MW-3 (June 7, 2022)	6.92	<1.0	13	4.4	0.011
MW-3 (Sept. 13, 2022)	6.8	5.2	8.9	.34	0.011
MW – 4 (June 18, 2020)	6.65	1.0	27	3.3	0.016
MW – 4 (Sept. 15, 2020)	6.80	1.0	35	5.1	0.009
MW-4 (June 21, 2021)	7.49	<1.0	15	1.0	<.005
MW-4 (Sept 9, 2021)	6.71	2.0	27	4.5	0.010
MW-4 (June 7, 2022)	7.47	<1.0	29	0.39	0.011
MW-4 (Sept. 13, 2022)	6.6	16	36	10	0.014

Notes:

1. Wastewater quality results are reported in milligrams per liter (ppm) unless otherwise specified.
2. Wastewater quality results are for samples from the splitter box (after septic tank).
3. NR = Not reported
4. Laboratory information from 2020 as reported by Green Mountain Engineering.
5. Laboratory sampling conducted by Vermont Utility Management Services (VTUMS)

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

5.0 WASTEWATER FLOW DATA

The treatment system average daily flows are estimated using individual water meter readings for each of the 34 customers connected to the system. The individual water meter readings for the 34 users connected to the Bristol Wastewater system were provided by the Town of Bristol. A summary of that data presented in Appendix C.

The average daily flow for the system for the 2022/2023 reporting period as measured from April 14, 2022 to April 11, 2023 was 7,793 gpd. Current and historic average daily flow information is summarized below in Table 7.

TABLE 7
BRISTOL WASTEWATER SYSTEM
HISTORIC AVERAGE DAILY FLOW

Year	Average Daily Flow (GPD)
*2020-2021	6,082
2021-2022	8,362
2022-2023	7,793

Two Year Average Daily Flow = 8,078 gpd

* 2021-2022 low flow data can be attributed to Covid shutdowns.

6.0 UNCOMMITTED RESERVE CAPACITY

The uncommitted reserve capacity of the system is based upon daily maximum BOD⁵ and TSS loading. The calculations for loading capacity are outlined in the Permit. A copy of the Uncommitted Reserve Capacity calculations are contained in Appendix D. The total maximum allowable BOD⁵ AND TSS loadings per the Discharge Permit are 33.4 lb/day and 25.0 lb/day respectively. The previous three years of flow data were utilized for calculating the average BOD⁵ and TSS loadings. The actual loadings based on the three-year flow average were 33.1 and 5.4 lb/day respectively, which are less than the allowable maximum permit limits. From a practical standpoint however, there is no additional uncommitted reserve capacity remaining in the system.

7.0 SUMMARY AND CONCLUSION

The wastewater system is in its 30th year of operation. The wastewater collection, treatment and disposal portions of the system are in good working condition. Some minor maintenance items are necessary as summarized herein.

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

As previously noted, there is no additional uncommitted reserve capacity in the system at this time due to elevated BOD⁵. The Town of Bristol is aware of this limitation and has indicated that they are in the process of hiring an engineering consultant to assist them with evaluating potential pre-treatment technologies with a goal of reducing BOD⁵.

Laboratory testing results show that the wastewater effluent and groundwater sampling parameters are within the historical range of values which would be expected. Nitrite levels in the groundwater samples should continue to be monitored to note any spikes or an increasing trend line.

Current recommended maintenance and repair issues include:

- a. Continue to utilize the routine system maintenance checklists outlined in the O&M Manual
- b. Complete the recommended collection and treatment system maintenance items listed in Tables 2 & 3.
- c. Cell #1 and Cell #2 of the septic tank should be pumped.
- d. Quarterly monitoring of the grease levels in the septic tank. If excessive grease buildup continues, the septic tank pumping frequency should be increased to more than once per year.
- e. Confirmation that the restaurants connected to the wastewater system are maintaining their interior grease traps on a regular basis.
- f. When pumping the exterior restaurant grease traps, confirm and document the size and configuration of each of the grease traps. Confirm that the grease traps contain baffles and are designed to function as grease traps, not septic tanks.
- g. Re-build the septic tank outlet trough.
- h. Remove the remaining box alder trees that continue to encroach on the disposal fields.
- i. USGS elevations should be determined for the top of Wells #2, #3 and #4 as well as the shallow monitoring wells within the disposal field. Subsequent water depth data should include USGS elevations.
- j. A stormwater or groundwater drainage line was observed to be discharging near field #1. Ditching should be conducted near the base of the bank to encourage the water to flow away from the disposal fields.
- k. Continue to monitor the splitter box flows regularly. Clean the v-notches with a brush regularly to ensure equal flow to each of the disposal fields.
- l. Replace the existing dosing siphon counters with mechanical counters when practical.
- m. Verify proper operation of the dosing syphons.
- n. Continue regular mowing and trimming of the disposal field area.
- o. Install locks on the covers of the four deep monitoring wells.
- p. Continue with efforts to evaluate pre-treatment technologies to reduce BOD⁵

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

APPENDIX A

Figures


Figures 1 & 2 - Collection System Component Locations

Figure 3 - Disposal Area Components

Figure 4 - Septic Tank Detail


VTM ENGINEERING, PLC


2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531



VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531






- NOTES:
1. ALL PIPES IN SEPTIC TANK TO BE 8" SCHEDULE 40 SOLVENT CEMENT PVC.
 2. ALL ANCHOR BOLTS AT SEPTIC TANK TO BE STAINLESS STEEL.



Outlet Pipe Observation Port

SCALE: NONE




LINK SEAL WALL SLEEVE

SCALE: NONE



SEPTIC TANK - PLAN VIEW
SCALE 1/8\"/>



VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

APPENDIX B

2022 Wastewater Discharge and Monitoring Well Sampling Results

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531



Page 1 of 2

Bristol, Town of	
PO Box 249	070294
Bristol, VT 05443	
Attn: Cyrus Marsano	

PROJECT: Bristol Core Area Sewer
 WORK ORDER: 2206-14573
 DATE RECEIVED: June 07, 2022
 DATE REPORTED: June 23, 2022
 SAMPLER: Jill Marsano

Laboratory Report

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. All required method quality control elements including instrument calibration were performed in accordance with method requirements and determined to be acceptable unless otherwise noted.

The column labeled Lab/Tech in the accompanying report denotes the laboratory facility where the testing was performed and the technician who conducted the assay. A "W" designates the Williston, VT lab under NELAC certification ELAP 11263; "R" designates the Lebanon, NH facility under certification NH 2037 and "N" the Plattsburgh, NY lab under certification ELAP 11892. "Sub" indicates the testing was performed by a subcontracted laboratory. The accreditation status of the subcontracted lab is referenced in the corresponding NELAC and Qual fields. The Williston, VT facility is also ISO/IEC 17025:2017 accredited for Total Coliform and E coli by SM9223B.

The NELAC column also denotes the accreditation status of each laboratory for each reported parameter. "A" indicates the referenced laboratory is NELAC accredited for the parameter reported. "N" indicates the laboratory is not accredited. "U" indicates that NELAC does not offer accreditation for that parameter in that specific matrix. Test results denoted with an "A" meet all National Environmental Laboratory Accreditation Program requirements except where denoted by pertinent data qualifiers. Test results are representative of the samples as they were received at the laboratory.

Endyne, Inc. warrants, to the best of its knowledge and belief, the accuracy of the analytical test results contained in this report, but makes no other warranty, expressed or implied, especially no warranties of merchantability or fitness for a particular purpose.

Reviewed by:

Harry B. Locker, Ph.D.
 Laboratory Director

www.endynelabs.com



160 James Brown Dr., Williston, VT 05495
 Ph 802-879-4333 Fax 802-879-7103

56 Etna Road, Lebanon, NH 03766
 Ph 603-678-4891 Fax 603-678-4893



VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

Laboratory Report

DATE REPORTED: 06/23/2022

CLIENT: Bristol, Town of
PROJECT: Bristol Core Area SewerWORK ORDER: 2206-14573
DATE RECEIVED: 06/07/2022

001	Site: Splitter Box		Date Sampled: 6/7/22		Time: 10:20		
Parameter	Result	Units	Method	Analysis Date/Time	Lab/Tech	NELAC	Qual
pH per Client	6.32	SU at 21.9C	Client Data	6/7/22 10:20	W CLI	N	
BOD-5day	670	mg/L	SM 5210B(16)	6/8/22 9:06	W JSS	A	
Chloride	60	mg/L	EPA 300.0	6/9/22 7:26	W ECM	A	
Nitrate as N	< 0.020	mg/L	EPA 300.0	6/8/22 20:25	W ECM	A	
Nitrite as N	< 0.020	mg/L	EPA 300.0	6/8/22 20:25	W ECM	A	
TKN	50	mg/L	EPA 351.2, R.2(1993)	6/14/22	N MAP	A	
Phosphorus, Total Dissolved	4.8	mg/L	SM20 4500 P-F	6/22/22 16:53	R RLS	A	
Solids, Total Suspended	86	mg/L	SM 2540 D-15	6/8/22	W JSS	A	
Oil & Grease Total Recoverable	31.3	mg/L	EPA 1664A	6/9/22	W ECM	A	

002	Site: MW #3		Date Sampled: 6/7/22		Time: 10:00		
Parameter	Result	Units	Method	Analysis Date/Time	Lab/Tech	NELAC	Qual
pH per Client	6.92	SU at 15.1C	Client Data	6/7/22 10:00	W CLI	N	
E. coli	< 1.0	MPN/100ml	SM 9223B(16)	6/7/22 14:59	W TEL	A	
Chloride	13	mg/L	EPA 300.0	6/8/22 21:45	W ECM	A	
Nitrate as N	4.4	mg/L	EPA 300.0	6/9/22 7:46	W ECM	A	
Phosphorus, Total Dissolved	< 0.011	mg/L	SM20 4500 P-F	6/22/22 16:54	R RLS	A	

003	Site: MW #4		Date Sampled: 6/7/22		Time: 10:10		
Parameter	Result	Units	Method	Analysis Date/Time	Lab/Tech	NELAC	Qual
pH per Client	7.47	SU at 14.7C	Client Data	6/7/22 10:10	W CLI	N	
E. coli	< 1.0	MPN/100ml	SM 9223B(16)	6/7/22 14:59	W TEL	A	
Chloride	29	mg/L	EPA 300.0	6/8/22 22:05	W ECM	A	
Nitrate as N	0.39	mg/L	EPA 300.0	6/8/22 22:05	W ECM	A	
Phosphorus, Total Dissolved	< 0.011	mg/L	SM20 4500 P-F	6/22/22 11:08	R RLS	A	

**VTM ENGINEERING, PLC**2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531



Page 1 of 2

Bristol, Town of	
PO Box 249	070294
Bristol, VT 05443	
Attn: Cyrus Marsano	

PROJECT: Bristol Core Area Sewer
 WORK ORDER: 2209-25919
 DATE RECEIVED: September 13, 2022
 DATE REPORTED: September 27, 2022
 SAMPLER: Jill Marsano

Laboratory Report

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. All required method quality control elements including instrument calibration were performed in accordance with method requirements and determined to be acceptable unless otherwise noted.

The column labeled Lab/Tech in the accompanying report denotes the laboratory facility where the testing was performed and the technician who conducted the assay. A "W" designates the Williston, VT lab under NELAC certification ELAP 11263; "R" designates the Lebanon, NH facility under certification NH 2037 and "N" the Plattsburgh, NY lab under certification ELAP 11892. "Sub" indicates the testing was performed by a subcontracted laboratory. The accreditation status of the subcontracted lab is referenced in the corresponding NELAC and Qual fields. The Williston, VT facility is also ISO/IEC 17025:2017 accredited for Total Coliform and E coli by SM9223B.

The NELAC column also denotes the accreditation status of each laboratory for each reported parameter. "A" indicates the referenced laboratory is NELAC accredited for the parameter reported. "N" indicates the laboratory is not accredited. "U" indicates that NELAC does not offer accreditation for that parameter in that specific matrix. Test results denoted with an "A" meet all National Environmental Laboratory Accreditation Program requirements except where denoted by pertinent data qualifiers. Test results are representative of the samples as they were received at the laboratory.

Endyne, Inc. warrants, to the best of its knowledge and belief, the accuracy of the analytical test results contained in this report, but makes no other warranty, expressed or implied, especially no warranties of merchantability or fitness for a particular purpose.

Reviewed by:

Harry B. Locker, Ph.D.
 Laboratory Director



160 James Brown Dr., Williston, VT 05495
 Ph 802-879-4333 Fax 802-879-7103

www.endynelabs.com

56 Etna Road, Lebanon, NH 03766
 Ph 603-678-4891 Fax 603-678-4893



VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

Laboratory Report

DATE REPORTED: 09/27/2022

CLIENT: Bristol, Town of
PROJECT: Bristol Core Area SewerWORK ORDER: 2209-25919
DATE RECEIVED: 09/13/2022

001	Site: Splitter Box			Date Sampled: 9/13/22		Time: 11:15	
Parameter	Result	Units	Method	Analysis Date/Time	Lab/Tech	NEL-AC	Qual
pH per Client	6.6	SU at 22.8C	Client Data	9/13/22 11:15	W CLI	N	
BOD-5day	430	mg/L	SM 5210B(16)	9/15/22 8:41	W JSS	A	
Chloride	67	mg/L	EPA 300.0	9/13/22 14:57	W ECM	A	
Nitrate as N	< 0.20	mg/L	EPA 300.0	9/13/22 14:57	W ECM	A	
Nitrite as N	< 0.20	mg/L	EPA 300.0	9/13/22 14:57	W ECM	A	
TKN	69	mg/L	EPA 351.2, R.2(1993)	9/23/22	N CAL	A	
Phosphorus, Total Dissolved	7.2	mg/L	SM20 4500 P-F	9/26/22 17:02	R RLS	A	
Solids, Total Suspended	124	mg/L	SM 2540 D-15	9/19/22	W JSS	A	
Oil & Grease Total Recoverable	32.2	mg/L	EPA 1664A	9/14/22	W CLD	A	

002		Site: MW #3		Date Sampled: 9/13/22				Time: 10:30	
Parameter	Result	Units	Method	Analysis Date/Time	Lab Tech	NEL-AC	Qual		
pH per Client	6.8	SU at 13.5C	Client Data	9/13/22 10:30	W CLI	N			
E. coli	5.2	MPN/100ml	SM 9223B(16)	9/13/22 16:27	W AKJ	A	CL2A		
Chloride		mg/L	EPA 300.0	9/13/22 15:17	W ECM	A			
Nitrate as N	0.34	mg/L	EPA 300.0	9/13/22 15:17	W ECM	A			
Phosphorus, Total Dissolved	< 0.011	mg/L	SM20 4500 P-F	9/26/22 17:04	R RLS	A			

003	Site: MW #4		Date Sampled: 9/13/22		Time: 10:50		
Parameter	Result	Units	Method	Analysis Date/Time	Lab Tech	NEL-AC	Qual
pH per Client	6.6	SU at 13.7C	Client Data	9/13/22 10:50	W CLI	N	
E. coli	16	MPN/100ml	SM 9223B(16)	9/13/22 16:27	W AKJ	A	
Chloride	36	mg/L	EPA 300.0	9/13/22 15:37	W ECM	A	
Nitrate as N	10	mg/L	EPA 300.0	9/13/22 15:37	W ECM	A	
Phosphorus, Total Dissolved	0.014	mg/L	SM20 4500 P-F	9/26/22 16:28	R RLS	A	

Report Summary of Qualifiers and Notes

CL2A: Sample was identified and submitted as non-chlorinated water. The DPD Chlorine Check indicated that chlorine or other oxidizer was present. The sample did not smell of Chlorine, so analysis was performed. The DPD analysis is a more sensitive screen, but is susceptible to interference. The presence of Chlorine will kill bacteria and bias the results low. Please contact the laboratory with questions.

**VTM ENGINEERING, PLC**

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

Bristol Core Area Sewer

Endyne Inc. CQC
Prepared 5/23/22

2208-25919

Dilution: 1000:1
 From Correl: Dyrus Marsano
 Bristol, Town of
 PO Box 249
 Bristol VT 05443
 Ph (802) 453-2410
 from@endynelab.com

Cust # 0702

COREAREA/SHW

5/17/2021

Bristol, Town of
Bristol Core Area Sewer

Splitter Box

Sampled Date/Time: 9/13/22 @ 11:55am Sampler: Jill Marsano

pH Client Data: 6.6 Su @ 22.8°C

Oil & Grease	1 - 100ml Amber Glass and 1 - 8oz Amber Glass	<6C	100
Chloride	1 - 2 oz Plastic Anion	<6C	
Nitrate as N			
Nitrite as N			
HCl-titrey	1 - 1/2 gal Plastic	<6C	
Solids, Total Suspended			
TKN	1 - 100ml Plastic	<6C, NY Phos, H2SO4	
Phosphorus, Total Dissolved	1 - 100ml Clear Glass	<6C, Filter then preserve	

MW #3

Sampled Date/Time: 9/13/22 @ 10:30am Sampler: Jill Marsano

pH Client Data: 6.8 Su @ 13.5°C

E. coli	1 - 150ml Sterile Plastic	<10C, Na2S2O3 HCl2	
Chloride	1 - 2 oz Plastic Anion	<6C	
Nitrate as N			
Phosphorus, Total Dissolved	1 - 100ml Clear Glass	<6C, Filter then preserve	

MW #4

Sampled Date/Time: 9/13/22 @ 10:50am Sampler: Jill Marsano

pH Client Data: 6.6 Su @ 13.7°C

E. coli	1 - 150ml Sterile Plastic	<10C, Na2S2O3 HCl2	
Chloride	1 - 2 oz Plastic Anion	<6C	
Nitrate as N			
Phosphorus, Total Dissolved	1 - 100ml Clear Glass	<6C, Filter then preserve	

Relinquished by: Burt Marsano 9/13/22 12:55 Date Time
 Accepted by: Eileen L. Lacey 9/13/22 12:55 Date Time

Relinquished by: _____ Date Time
 Received by: _____ Date Time

Blank/Paramecium count as listed Client initials: _____

Client Authorization to use Submittal No. Client initials: _____

Sample origin: VI ☐ NH ☐ NY ☐ Other ☐

Special reporting instructions (PCR): _____

Requested turnaround time: Routine - Rush Date Time

Aqueous samples requiring metals testing require acid preservation for a 24 hr period prior to analysis.



100 James Brown Dr
 Windsor, VT 05440
 Ph: 802-979-4131
 Fax: 802-979-1130

88 Elmwood Road
 Lebanon, VT 05455
 Ph: 802-878-0991
 Fax: 802-878-4858

315 New York Rd.
 Portland, ME 04101
 Ph: 603-663-1720
 Fax: 603-663-0352

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
 spalmer@vtmengineering.com (802) 233-7531

APPENDIX C

2022/2023 Wastewater Treatment System Flow Data

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

2022-2023 Bristol Water Usage Summary (Wastewater District Only)

Revised 4-24-23

Month	Date Reading Started	Date Reading Ended	Total Monthly Water Usage (Gallons)
Apr-22	4/14/2022	5/11/2022	230,000
May-22	5/11/2022	6/14/2022	278,000
Jun-22	6/14/2022	7/12/2022	239,000
Jul-22	7/12/2022	8/12/2022	281,000
Aug-22	8/12/2022	9/14/2022	281,000
Sep-22	9/14/2022	10/12/2022	238,000
Oct-22	10/12/2022	11/11/2022	139,000
Nov-22	11/11/2022	12/16/2022	257,000
Dec-22	12/16/2022	1/23/2023	274,000
Jan-23	1/23/2023	2/13/2023	168,000
Feb-23	2/13/2023	3/13/2023	223,000
Mar-23	3/13/2023	4/11/2023	213,000

Total Annual Flow (Gallons) =	2,821,000
--------------------------------------	------------------

Monthly Average Flow (Gallons/Month) =	235,083
---	----------------

Total Number of Days in Survey =	362
---	------------

Average Flow Per Day (Gallons/Day)=	7,793
--	--------------

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

APPENDIX D

Uncommitted Reserve Capacity Calculations

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

Town of Bristol
Wastewater Reserve Capacity Calculations

Revised 4/26/23

Base Information

- * 1. Average Daily Flow 2020/2021 =
 2. Average Daily Flow 2021/2022 =
 3. Average Daily Flow 2022/2023 =

	Avg Annual Flow (gpd)	Avg Annual Flow (MGD)
	6,082	0.0060820
	8,362	0.0083620
	7,753	0.0077530
Long Term Avg. (gpd) =	7,412	0.0074123

	* 6/18/2020	* 9/15/2020	6/21/2021	9/9/2021	6/7/2022	9/13/2022	Long Term Average (mg/l)
3. AVG BOD 5 (mg/l) =	560	490	640	420	670	430	535
4. AVG TSS (mg/l) =	70	86	90	66	86	124	87

Calculations lbs/day Discharged

BOD 5 (lb./day) discharged = ADF x (BOD 5) x 8.34
 Calculated BOD 5 (lb./day) discharged =

33.1 lb./day Result < Permitted Capacity of 33.4 lb./day
 80% of 33.4 lb./day = 26.72 lb./day
 Result > 26.72 lb./day. Indicates no reserve capacity.

TSS (lb./day) discharged = ADF x TSS x 8.34
 Calculated TSS Discharged =

5.4 lb./day Result < Permitted Capacity of 25 lb./day

* Data as reported by Green Mountain Engineering

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531

APPENDIX E

Photographs

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531



Overview of the wastewater
distribution field



Septic tank access hatches



Splitter Box



Septic tank outlet trough

VTM ENGINEERING, PLC

2941 Shelburne Falls Road, Hinesburg, Vermont 05461
spalmer@vtmengineering.com (802) 233-7531