

ADDENDUM #4

Lincoln Road Riverbank Repair
Bristol, Vermont
July 20, 2023

QUESTIONS AND RESPONSES:

Q. Is grouting still part of the fishing platform project?

A. No. The grout is being removed from the project so just large riprap will be placed around the boulder in the upstream side of the scour hole at the platform.

Q. Is the arch foundation structure detail for the walkway just intended for the upstream end of the concrete walkway or will there be footing walls along the entire length of the concrete walkway?

A. The footing detail shall extend along the entire walkway.

Q. The two metal posts will be set in concrete bases like a bollard, but will the posts be concrete filled?

A. A concrete base is expected for the posts, but they do not have to be filled.

No other questions were received. All other conditions remain the same.

END OF ADDENDUM #4